


FOR REVIEW ONLY



A

SHRUB PLANTING DETAIL - SECTION VIEW

Relative Scale 1"=1' 0' 0.5' 1.0'
 Absolute Scale 1:12

GENERAL NOTES

- A CONTRACTOR IS RESPONSIBLE FOR PLANTING SHRUBS STRAIGHT AND BALANCED TO PROPER DEPTH ACCORDING TO DETAIL
- B CONTRACTOR IS TO NOTIFY THE LANDSCAPE ARCHITECT/DESIGNER OF ANY QUESTIONS, CONCERNS OR DISCREPANCIES BETWEEN NOTES, DRAWINGS, AND SITE CONDITIONS BEFORE PROCEEDING.
- C ENSURE THAT IRRIGATION IS SUFFICIENT PER SPECIES PLANTED. ONLY ONE TIME, AFTER SHRUB INSTALLATION, FILL IRRIGATION RING WITH WATER.
- D IF SOILS OR OTHER SITE CONDITIONS PREVENT PLANTING AS DETAILED, NOTIFY LANDSCAPE ARCHITECT/DESIGNER IMMEDIATELY.
- E INSTALL IRRIGATION DRIPPERS WITHIN BACKFILL MATERIAL, BETWEEN CANOPY EDGE AT FUTURE FULL GROWTH AND MIN. 6-IN AWAY FROM SHRUB BASE/TRUNK.
- F REFERENCES: 1) Chance Munns, cmunns@csi.edu, 2) Urban Tree Foundation (www.urbantree.org), 3) Landscape Architectural Graphic Standards by Hopper, 4) greenscapesinc.net/landscaping-fabric/

SHEET KEYNOTES

- 1 REMOVE TWINE, BASKET, BURLAP OR PLASTIC POT FROM ROOTBALL. REMOVE ALL NAILS/STAPES & TIES. ONLY BIODEGRADABLE BURLAP SHALL BE LEFT ON BOTTOM 1/3 OF ROOTBALL.
- 2 REMOVE DEAD, DYING OR DECAYED LIMBS AND DEBRIS BEFORE PLANTING.
- 3 SET ROOTBALL CROWN 1"-2" HIGHER THAN SURROUNDING FINISH GRADE. SLOPE BACKFILL AWAY FROM ROOTBALL FOR POSITIVE DRAINAGE TO PREVENT STANDING WATER FROM ACCUMULATING NEXT TO THE TRUNK/BASE.
- 4 APPLY MULCH AT 3-IN MIN. DEPTH AND 6-IN FROM BASE OF SHRUB UNLESS SPECIFIED OTHERWISE ON PLAN.
- 5 APPLY LANDSCAPE FABRIC OR PRE-EMERGENT HERBICIDE SPRAY AS SPECIFIED ON PLAN TO PROHIBIT GERMINATION OF WEEDS.
- 6 TO FACILITATE BINDING WITH NEW SOIL, ROUGHEN WALLS OF HOLE BEFORE PLANTING.
- 7 BACKFILL WITH APPROVED TOPSOIL USING 6-IN LIFTS. COMPACT BY TAMPING LIGHTLY TO BRACE SHRUB. FILL TO TOP OF ROOT BALL. POUR WATER AROUND THE ROOT BALL TO SETTLE.
- 8 SET ROOTBALL ON NATIVE UNDISTURBED SOIL.



CITY OF JEROME PUBLIC WORKS
 Richard Wuori, PE, Director
 152 East Avenue A
 Jerome ID 83338
<http://www.ci.jerome.id.us>

SHRUB PLANTING

STANDARD DRAWING NO.

SD-999

DATE 24 OCT 2017